

Annexure C

PROFORMA FOR SAFE DRINKING WATER AND SANITARY CONDITION CERTIFICATE

No.

Dated: 31.07.2026

It is certified that an inspection team headed by Shailendra Wakhle (Name of Officers with designation) from P.H.E Sub Division , Badnawar inspected the KASYAP VIDYAPEETH , CHETANYA GRAM , KHEDA , BADNAWAR Dist. Dhar (M.P.) (Name & Address of the school) on 17/07/2026 (date of inspection) and on the basis of Water Test Report (Attached) bearing no. DWTL/Dhar/No.239 dated 22.07.2026 of District Water Testing Laboratory PHED – Dhar (M.P.) (PHED Lab) certified that the KASYAP VIDYAPEETH (Name of school) has safe drinking water facilities for the students and members of staff of the institution. School is also maintains the hygienic sanitation condition in the school building & the campus as per norms prescribed by the Central/ State/ U.T. Govt.

This certificate is valid till 31/07/2027


Assistant Engineer
P.H.E. Sub Division
Badnawar, Dhar (M.P.)

Signature with Seal

Name : Shailendra Wakhle

Designation : A.E.(P.H.E.)

Name & Address of the Office / Department : P.H.E. . BADNAWAR Dist.DHAR (M.P.)

To

KASYAP VIDYAPEETH
CHETANYA GRAM , KHEDA
BADNAWAR Dist.DHAR (M.P.)
(Name & Address of the Institution)

Note: The certificate is to be issued by authorized officer / PHED Lab / local bodies

District Water Testing Laboratory

P.H.E.D. Dhar (M.P.)

phelabdhara@gmail.com

Water Testing Report

DWTL/Dhar No 239 Date 22/07/2026 Your Ref :-No KVP/Water testing/2026 dt 17.07.2026

Samples From :- KASYAP VIDYAPEETH, CHETANYA GRAM, BADNAWAR, DHAR

1) R.O WATER FROM SCHOOL

Date of Receipt :- 20.07.2026

Date of Start of Analysis :- 20.07.2026

Date of Completion of Analysis :- 20.07.2026

Sample collected and submitted by the customer

S.No.	Parameters	Test method	BIS 10500:2017 Desirable/Permissible Limit and Unit	Result			
				R.O WATER			
1	Colour	IS 3025 part 4	5/15 Co.Pt Scale	0			
2	Odour	IS 3025 part 5	Acceptable	Acceptable			
3	Turbidity	IS 3025 part 10	1.0/5.0 NTU	0.30			
4	pH	IS 3025 part 11	6.5 – 8.5 pH Scale	6.98			
5	Specific Conductivity	IS 3025 part 14	Micro mhos/cm	112			
6	Total Dissolved Solids	IS 3025 part 16	500 / 2000 mg/Lit.	72			
7	Total Hardness (as CaCO ₃)	IS 3025 part 21	200 / 600 mg/Lit.	38			
8	Calcium	IS 3025 part 40	75 / 200 mg/Lit.	9.6			
9	Magnesium	IS 3025 part 46	30 / 100 mg/Lit.	3.4			
10	Sulphate (as SO ₄)	IS 3025 part 24	200 / 400 mg/Lit.	2			
11	Total Alkalinity	IS 3025 part 23	200 / 600 mg/Lit.	34			
12	Chlorides (as Cl)	IS 3025 part 32	250 / 1000 mg/Lit.	11			
13	Fluorides (as F)	IS 3025 part 60	1.0 / 1.5 mg/Lit.	0.10			
14	Nitrates (as NO ₃)	APHA 23 Edition 4500B UV	45/ 45 mg/Lit.	2			
15	Iron (as Fe)	IS 3025 part 53	0.3/ 0.3 mg/Lit.	0			
16	Manganese	IS 3025 part 59	0.1 / 0.3 mg/l	0			
17	Residual Chlorine	VCM	0.2 mg/Lit. at Consumer point				
18	Total Coliform	APHA 22 Edition 9211B	0 / 0	0			
19	Faecal Coliform	APHA 22 Edition 9211B	0/ 0	0			

Remarks:- All the tested parameters are within the Desirable limits as per BIS 10500 - 2012 in the given sample.


P.H.E.D. Dhar (M.P.)
Dist. Water Testing Laboratory
P.H.E. Dhar (M.P.)